

प्रेषक

नितेश कुमार झा
अपर सचिव
उत्तराखण्ड शासन

सेवा में

निदेशक
आई0टी0डी0ए0
93,फेस-II, वरान्त विहार
देहरादून

सूचना प्रौद्योगिकी विभाग

देहरादून दिनांक: 10 दिसम्बर 2009

विषय:— जिला चमोली के अन्तर्गत स्वान पी0ओ0पी0 केन्द्रों हेतु अतिरिक्त कार्यों के लिये
धनराशि अवमुक्त करने के सम्बन्ध में।

महोदय,

परियोजना प्रबन्धक, निर्माण यूनिट, उत्तराखण्ड पेयजल निगम गोपेश्वर (चमोली) ने अपने पत्र दिनांक 30.10.2009 द्वारा जिला मुख्यालय, उप जिला मुख्यालयों एवं विकास खण्ड मुख्यालयों में स्वान पी0ओ0पी0 केन्द्रों के निर्माण में पूर्व स्वीकृत प्राक्कलन से अतिरिक्त कार्यों के निर्माण हेतु धनराशि रु0 25.89 लाख के आगणन शासन में उपलब्ध कराये। प्राप्त आगणनों का परीक्षण टी0ए0सी0 वित्त विभाग से कराया गया। टी0ए0सी0 वित्त विभाग ने आगणनों की धनराशि रु0 25.89 लाख के सापेक्ष औचित्यपूर्ण धनराशि रु0 23.76 लाख पर अपनी स्वीकृति प्रदान की है।

2. उक्त स्वीकृति निम्नलिखित प्रतिबन्धों के साथ प्रदान की जाती है:—

- I. कार्य करने से पूर्व मदवार दर विश्लेषण विभाग के अधीक्षण अभियन्ता द्वारा स्वीकृत/अनुमोदित दरों के आधार पर तथा जो दरें शेड्यूल ऑफ रेट्स में स्वीकृत नहीं है अथवा बाजार भाव से ली गयी हो, की स्वीकृति नियमानुसार अधीक्षण अभियन्ता से अनुमोदन करना आवश्यक होगा।
- II. कार्य करने से पूर्व विस्तृत आगणन/मानचित्र गठित कर नियमानुसार सक्षम प्राधिकारी से प्राविधिक स्वीकृति प्राप्त करनी आवश्यक होगी।
- III. कार्य पर उतना ही व्यय किया जाये जितनी राशि स्वीकृत की गयी है। स्वीकृत धनराशि से अधिक व्यय कदापि न किया जाय।
- IV. एक मुश्त प्राविधानों को कार्य करने से पूर्व विस्तृत आगणन गठित कर सक्षम अधिकारी से अनुमोदन प्राप्त कर लिया जाय।

- V. कार्य करने से पूर्व समस्त औपचारिकताएं तकनीकी दृष्टि को मध्यनजर रखते हुए एवं लॉ0गि0वि0 द्वारा प्रचलित दरों/विशिष्टियों को ध्यान में रखते हुए निर्माण कार्य को सम्पादित करना सुनिश्चित करें।
- VI. कार्य करने से पूर्व उच्चाधिकारियों एवं भूगर्भवेत्ता (कार्य की आवश्यकतानुसार) से कार्य स्थल का भूली-भौति निरीक्षण अवश्य करा लिया जाय तथा निरीक्षण के पश्चात दिये गये निर्देशों के अनुरूप ही कार्य कराया जाय।
- VII. निर्माण सामग्री को उपयोग में लाने से पूर्व सामग्री का परीक्षण प्रयोगशाला से अवश्य करा लिया जाय तथा उपयुक्त सामग्री को ही प्रयोग में लाया जाय।
- VIII. मुख्य सचिव, उत्तराखण्ड शासन के शासनादेश संख्या 2047/XIV-219(2006) दिनांक 30.05.2006 द्वारा निर्गत आदेशों का कार्य करते समय या आगणन गठित करते समय कड़ाई से पालन करने का कष्ट करें।
- IX. आगणन गठित करते समय तथा कार्य प्रारम्भ कराने से पूर्व Uttarakhand Procurement Rules 2008 का अनुपालन सुनिश्चित किया जाय।
3. टी0ए0सी0 वित्त विभाग द्वारा परीक्षणोपरान्त उपलब्ध कराई गई आख्या संलग्न कर प्रेषित की जा रही है।
4. इस सम्बन्ध में मुझे यह कहने का निदेश हुआ है कि कृपया जिलाधिकारी, चमोली को स्वान योजना से सम्बन्धित उपरोक्त कार्यो हेतु धनराशि रु0 23.76 लाख अवमुक्त करने का कष्ट करें।

संलग्नक:- यथोक्त।

भवदीय

(नितेश कुमार झा)
अपर सचिव

पृष्ठांकन संख्या:-4/40/20/XXXIV/सू0प्रौ0/2009 तद्दिनांकित
प्रतिलिपि निम्नलिखित को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित:-

1. जिलाधिकारी, चमोली।
2. राज्य सूचना अधिकारी, एन0आई0सी0, सचिवालय परिसर, देहरादून।
3. परियोजना प्रबन्धक, निर्माण यूनिट, उत्तराखण्ड पेयजल निगम, गोपेश्वर, चमोली।
4. गार्ड फाईल।

आज्ञा से

-X-
(हरिओम)
संयुक्त सचिव

UTTRAKHAND PEYJAL SANSADHAN
VIKAS EVAM NIRMAN NIGAM



SUPPLEMENTARY ESTIMATE FOR
ADDITIONAL WORK OF POP
CENTER'S UNDER SWAN PROJECT

DISTRICT : CHAMOLI

ESTIMATED COST- Rs **25.89** Lacs
YEAR - 2009 - 10
ESTIMATE NO. -

PROJECT MANAGER
NIRMAN WING
UTTRAKHAND PEYJAL NIGAM
GOPESHWAR

R 25.64 Lacs


SUPPLEMENTARY ESTIMATE FOR ADDITIONAL WORK OF POP CENTER'S UNDER SWAN PROJECT

District- Chamoli.

Form - 'J'

Sl. No.	Description	Percentage	Cost (Rs. in Lacs)
1	Cost of works	-	23.54
2	Add departmental centage @ 10.00% on Sub Total	10.00%	2.35
		Total Rs.	25.89

Prepared by



A.R.E.

Checked by




Computer

Approved by



Project Manager

Construction Wing, Uttarakhand Pwaj Nigam, Gopeshwar.

Countersigned By


(AVADITESH KUMAR)
(General Manager)
Uttarakhand Pwaj Nigam
Const- wing, Shri Nagar
(Gopeshwar)

Additional Aluminum Partition & False Ceiling

General Abstract of Cost

S.N.	Name of PoP Center	Additional Aluminum Partition	Generator Shed	Cartage of Furniture	Additional Electric Works	Fire Extinguisher Equipment
1	2	3	4	5	6	7
1	Karnprayag (THQ)	17660.45	75000.00	1879.80	135000.00	6000.00
2	Narayanbagar (BHQ)	19390.55	75000.00	2115.00	135000.00	6000.00
3	Gairsam (THQ)	34088.50	75000.00	2299.80	135000.00	6000.00
4	Ghat (BHQ)	26397.85	75000.00	2283.00	135000.00	6000.00
5	Dewal (BHQ)	70716.85	75000.00	2467.80	135000.00 -	6000.00
6	Pokhari (THQ)	14378.00	75000.00	2115.00	135000.00	6000.00
7	Chamoli (THQ)	-7702.50	0.00	2131.80	135000.00	6000.00
8	Tharali (THQ)	17775.00	75000.00	2283.00	135000.00	6000.00
9	Joshimath (THQ)	16590.00	75000.00	2215.80	135000.00	6000.00
10	Gopeshwar (BHQ)	22104.20	0.00	2551.80	135000.00 -	6000.00
	TOTAL	231398.90	600000.00	22342.80	1350000.00	60000.00
	Say	2.31	6.00	0.22	13.50 -	0.60
Total						22.64
Contingencies 4% on Total						0.905
Grand Total						23.54

A.R.E.

Additional Aluminum Partition & False Ceiling **Abstract of Cost**

[illegible]

Estimate for Construction of Generator Shed

Abstract of Cost

S.N.	Name of PoPs Centre	Nos.	As per P.E. (Sanctioned)	As per Actual (Proposed)	Rate (in Laes)	Additional Expenditure
1	2		3	4		5
1	Karnprayag (THQ)	1	-	1	0.750	0.750
2	Narayanbagar (BHQ)	1	-	1	0.750	0.750
3	Gairsain (THQ)	1	-	1	0.750	0.750
4	Ghat (BHQ)	1	-	1	0.750	0.750
5	Dewal (BHQ)	1	-	1	0.750	0.750
6	Pokhari (THQ)	1	-	1	0.750	0.750
7	Chamoli (THQ)	1	1	-	0.750	0.000
8	Tharali (THQ)	1	-	1	0.750	0.750
9	Joshimath (THQ)	1	-	1	0.750	0.750
10	Gopeshwar (DHQ)	1	1	-	0.750	0.000
	ToTAI				7.50	6.00

Note:- The rate of Rs 75000.00 is approved in Chamoli P.E. (अनुमति)


A.R.E.


Computer


Project Manager

Additional Electrical Works
Abstract of Cost of one PoP Centre
(Electrical Works)


S. N.	Description	Schedule	Qty.			Unit	Rate (Rs.)	Amount (Rs.)
			As per P.E.	As per Actual	Balance / Additional			
	WIRING POINTS							
1	Wiring points for light with 1.5 sqm P.V.C. insulated single core cable heavy gauge rigid steel conduit pipe partly concealed in wall & partly laid in slab along with the reinforcement before concreting complete with 8 S.W.G. G.I. Earth continuity wire & Piano type switch etc. complete in all respect.	138.00	4.00	10.00	6.00	Nos.	280.00	1680.00
2	Same as above item no 1 but for fan and light duty exhaust fan.	140.00	2.00	5.00	3.00	Nos.	410.00	1230.00
3	Same as above item no 1 but for 5 amp. plug point on box	141.00	1.00	5.00	4.00	Nos.	200.00	800.00
1	Same as above item no 1 but for 5A plug point separate	141.00	6.00	26.00	20.00	Nos.	460.00	9200.00
2	Supply & fixing of telephone socket with all respect			2.00		Nos.	340.00	680.00
	MAINS & SUBMAINS							
1	Supply & wiring of submain 2 nos. 10 sqm P.V.C. insulated 1100 volts grade single core copper conductor cable in 19mm diameter heavy PVC conduit partly concealed in wall and partly laid in slab along with the reinforcement before concreting completely with one number 8 S.W.G.G.I. Earth continuity wire completely in all	2243.00		50.00		Mtr.	160.00	8000.00
2	Same as above item no. 1 but for 2 nos. 6.0 Sqm.	2241.00		10.00		Mtr.	140.00	1400.00
3	Same as above item no. 1 but for 2 nos. 4 Sqm.	2241 (A)	10.00	80.00	70.00	Mtr.	100.00	7000.00
4	Same as above item no. 1 but for 2 nos. 2.5 Sqm.	2241 (B)	15.00	50.00	35.00	Mtr.	90.00	3150.00

DISTRIBUTION BOARDS, SWITCHES & MINIATURE CIRCUIT BREAKERS								
1	(i) S/F of 6/32 amp. MCB 9 KA/10 KA	1002.00	4.00	25.00	21.00	Nos.	170.00	3570.00
	(ii) S/F of 40A 2 pole isolator	1006.00	1.00	3.00	2.00	Nos.	600.00	1200.00
	(iii) S/F of 63A 4 pole isolator	1007.00		1.00		Nos.	750.00	750.00
	(iv) S/F of 40A 2 pole RCCB	1007.00	1.00	3.00	2.00	Nos.	2000.00	4000.00
2	S/F of surface/flush mounting SPN distribution board without MCB complete in all respects as directed at site							
	(a) 4 ways SPN	1024.00		1.00		Nos.	2800.00	2800.00
	(b) 12 ways SPN	1024.00		1.00		Nos.	1500.00	1500.00
	(c) 10 ways SPN	1024.00		1.00		Nos.	1200.00	1200.00
3	S/F of power plug with 15amp. 250 volts flush type sockets in suitable M.S. box of 175mmx100mm size with bakelite sheet cover 3mm thick fixed with brass machine screws & washers complete in all respect.	1139.00	4.00	21.00	17.00	Nos.	520.00	8840.00
EARTHING								
1	Supply & burrying of 600 x 600 x 3.0 mm Copper Plate vertically for earthing with its top at least 3m below ground level complete 20m dia G.I. Pipe and funnel for watering and two earthing lead of no. 8 to 10 SWG G.I. Wire in 12mm dia G.I. Pipe upto switch board (From apron to switch the cost of GI Pipe and CU wire will be extra) 300mm square G.I. Box with hinged Cover.	705.00		1.00		Nos.	15000.00 L.S	15000.00 6200.00
2	Supply & burrying of 600 x 600 x 6.0 mm G.I. Plate vertically for earthing with its top at least 3m below ground level complete 20m dia G.I. Pipe and funnel for watering and two earthing lead of no. 8 to 10 SWG G.I. Wire in 12mm dia G.I. Pipe upto switch board (From apron to switch the cost of GI Pipe and GI wire will be extra) 300mm square G.I. Box with hinged Cover	705.00		1.00		Nos.	5000.00	3500.00 5000.00
UNDER GROUND CABLES								

1	Supply and laying of aluminium conductor PVC insulated armored served, sheathed able 100 volts grade at 750mm below ground level over a cushion of 75mm thick sand around & protected with brick on sides & top on surface the cable run shall be fixed on M.S. Clamps etc. of durable size complete in all respect. The armoring of the cable shall be properly connected with the earth conductor by the clamps etc.							
	(1) 16 Sqm. 2.00 core	501.00	30.00	110.00	80.00	Mtr.	240.00	19200.00
		Total Schedule Item Rs.						96200.00
	LIGHTING FIXTURES AND FANS FITTINGS							
1	S/F of ceiling light 3 x 36 W CFL fitted in fall ceiling complete in all respect.		1.00	3.00	2.00	Nos.	3200.00	6400.00
2	S/F of wall mounted fan complete in all respect		2.00	5.00	3.00	Nos.	1700.00	5100.00
3	S/F of 1 x 40 W Box Type Tube fitting complete in all respect			1.00		Nos.	500.00	500.00
4	S/F of 23W CFL complete in all respect.		1.00	4.00	3.00	Nos.	240.00	720.00
5	Charge for Electrical Connection from Hydle (letter Attach)						16000.00	16000.00
6	S/F of Single Phase Changeover					1 Nos		950.00
7	S/F of Automatic Changeover 3-Phase					1 Nos		4500.00
		Total Non Shedule Item Rs.						34170.00
		Total Schedule & Non Schedule Item Rs.						130370.00
		Say in Lacs						1.30
		Add 4% Contingencies						0.05
		Rs. In Lacs						1.35



Y.P. Singh
(Assistant Resident Engineer)



Satish Kumar
(Project Manager)